

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

Received for record the  
21<sup>st</sup> day of JULY  
 A. D. 1995 at 1:40 o'clock  
P m., and recorded in  
 Liber 5 of CORNERS  
 on page 278.  
*Ramona Collins Deputy*  
 Register of Deeds

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                    |                           |              |
|------------------------------------|---------------------------|--------------|
| 1. Public Land Survey              | T <u>47N</u> R <u>47W</u> | <u>C-D-3</u> |
|                                    | T _____ R _____           | <u>007</u>   |
|                                    | T _____ R _____           |              |
|                                    | T _____ R _____           |              |
| 2. Property Controlling in Section | S _____ T _____ R _____   |              |
|                                    | S _____ T _____ R _____   |              |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   |              |
|                                    | S _____ T _____ R _____   |              |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 Meander corner common to Sections 5 and 8, T47N, R47W

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John R. Garske, in a field survey on April 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- On August 30, 1848, William Ives set a post from which a 14" hemlock bears S15°E, 36 links and an 8" hemlock - N45°E, 19 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of this corner exists. I reestablished the corner position by extending the section line common to Sections 5 and 8 until intersecting the bank of the Montreal River. I believe that this is the most probable location for this corner as it lies in harmony with local residents.

Record research on file with Register of Deeds.

**PEER GROUP APPROVED**  
*Richard L. Drabin 7/18/95*  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set a 2 1/2" diameter x 30" long aluminum pipe with a 3 1/4" diameter aluminum cap stamped: County Remonumentation; T47N, R47W; M.C.; S-5; S-8; 1995; R.L.S. 28410, from which I established the following bearing trees and/or reference object:  
 9" hemlock - N63°E - 11.57 feet  
 7" sugar - S03°W - 7.41 feet  
 6" hemlock - N55°W - 2.63 feet  
 6' steel rail with sign - S60°E - 1.90 feet  
 Top of bank - due west - 6.5 feet  
 Edge of river - due west - 14.5 feet



Signed by John R. Garske Date 5-4-95  
 Surveyor's Michigan License No. 28410