

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the

16 day of SEPT
 A. D. 1994 at 4:10 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 132
Ramona Collins, Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>47N</u> R <u>47W</u>	H-I-11
	T _____ R _____	<u>009</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Meander corner common to Sections 27 & 34, T47N, R47W.

I, John R. Garske, in a field survey on June 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- Original survey by William Ives, D.S., in 1848. Set wood post. Original bearing trees: Fir 8" - S30°E, 4 links; Fir 6" - N77°E, 19 links.
- 1969 survey by T. Nelson shows section line but no meander corner.
- 1991 survey for the City of Ironwood of the "Norrie Park" area by J.R. Garske, RLS 28410. Set 1" diameter iron pipe. Established the following bearing trees: 13" pine - N80°E, 8.90 feet; 12" pine - S10°E, 5.96 feet; 12" pine - N86°W, 6.01 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found 1" iron pipe from 1991 survey and checked with witness. Corner was set by extending the north section line (in the centerline of road) of Section 35, T47N, R47W, west to the Montreal River. I updated corner as noted below to bring it up to county and state specifications.

Research record form on file with County Register of Deeds Office.

PEER GROUP

Approved

Richard L. Drahn

9/14/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" brass cap with a 2" stem set in concrete atop the found 1" iron pipe which I also encased in concrete. The cap is stamped: M.C., S-27, S-34, T47N, R47W, 1994, RLS 28410. I established the following bearing trees and reference objects: Existing red pine 12" - N86°W, 6.01 feet; existing R. pine 13" - N80°E, 8.90 feet; existing J. pine 12" - S10°E, 5.96 feet; R. pine 9" - N07°W, 27.24 feet; steel sign posts - N40°E, 2.02 feet.



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 8/31/94