

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic Located In: Corner Code #
(County)

1. Public Land Survey T 48N R 45W. M-4
T _____ R _____
T _____ R _____
T 48N R 44W A-4
S _____ T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Received for record the
26TH day of AUGUST
A. D. 1999 at 1:45 o'clock
7 m., and recorded in
Liber 7 of CORNERS
on page 238
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 12 & 7; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on August 21, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/8/1847. Original bearing trees:

Black Ash	10"	S.86° W.	26 links	(17.16')
Black Ash	12"	N.64° E.	18 links	(11.88')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the two original bearing trees. The first one is a large mound of extremely badly decayed hardwood, (species undetermined). The second one is now a downed 12" Black Ash sprout and portions of the original parent stump.

The 1.50 chain distance south to "enter swamp, NE" and the 4.50 chain distance north to "leave swamp, NE" are both in accordance with the field notes of the original Government survey.

A 3/4" X 2' iron pipe set by Gogebic County Forestry Commission by compass and chain bears S.87° W., 16.0'.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" X 4' aluminum rod monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Black Ash	9"	N.19° E.	10.91'
Black Ash	10"	S.12° E.	10.42'
Red Maple	6"	N.74° W.	11.91'
Steel sign rail	6'	S.84° E.	2.40'

PEER GROUP APPROVED

Richard L. Drahn 8/24/99
COUNTY REGISTER



Signed by Richard L. Drahn Date August 23, 1999
Surveyor's Michigan License No. 21564