

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office } ss.
Gogebic County }

SECTION

For corners in

Received for record the
26th day of AUGUST
A. D. 1999 at 1:45 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 239
Ramona Collins, Deputy
Register of Deeds

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45 W.</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>48N</u> R <u>44W</u>	<u>A-6</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter Corner 13 & 18; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on July 11, 1994 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/8/1847. Original bearing trees:
Sugar 12" S.83° W. 9 links (5.94')
Hemlock 6" N.66° E. 21 links (13.86')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence remains of the original corner or accessories.

Corner position re-established by single proportionate methods, on line between and equal distance from the northeast and southeast corners of section 13, T.48 N., R.45 W.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Sugar Maple	13"	N.30° W.	4.92'
Sugar Maple	10"	N.71° E.	21.44'
Sugar Maple	12"	S.35° E.	13.94'
Steel sign rail	6"	S.47° W.	2.02'

PEER GROUP APPROVED

Richard L. Drahn 8/24/99
COUNTY REGISTER



Signed by Richard L. Drahn Date August 10, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1986