

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 48N R 45W M-7

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T 48N R 44W A-7

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Section Corner 13, 24, 18 & 19; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on July 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/8/1847. Original bearing trees

Hemlock 10" S.23° E. 15 links (9.90')

Elm 10" N.38° W. 31 links (20.46')

Limpert and Kellan, on 4/8/35 recovered a scribed Sugar witness tree 25' SW of the corner

Corner restored by Donald D. Lappala, RLS 12585 on 5/3/71 from the remains of the two original B.T.s. He set a 2 1/2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s:

Sugar Maple 5" N.50° W. 24.9'

Sugar Maple 5" N.47 1/2° E. 13.5'

Sugar Maple 12" S.30° W. 16.0'

Corner recorded in Gogebic County USFS Liber, Page N-1 on 8/10/72.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the corner as described and the bearing trees as follows:

Sugar Maple 7" N.52° W. 16.04' (new nail)

Sugar Maple 6" N.46° E. 13.51' (new nail)

Red Maple 17" S.27° W. 24.81' (new nail)

The original Hemlock B.T. is now a decayed Hemlock stump with the reverse impression of the measuring notch. The Elm B.T. is now a very large windthrown stump hole. The Sugar W.T. recovered scribed in 1935 is now a series of root holes with Sugar wood bearing S.46° W. 20.9'.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

Steel sign rail 6' S.48° E. 2.81'

Steel sign rail 6' N.48° W. 2.82'

FREE GROUP APPROVAL  
Richard L. Drahn 7/20/99  
COUNTY APPROVAL

Signed by Richard L. Drahn

Date July 19, 1999

Surveyor's Michigan License No. 21564

Register's Office }  
Gogebic County } ss.

Received for record the  
21<sup>st</sup> day of JULY  
A. D. 1999 at 1:15 o'clock  
7 m., and recorded in  
Liber 7 of CORNERS  
on page 193  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

