

**SURVEY & REMONUMENTATION**

*map COMP*

JUN 29 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>48N</u> R <u>44W</u> | <u>A-8</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 Corner 19 & 24; T.48N., R.44-45W.

Register's Office } ss.  
Gogebic County }

Received for record the  
2<sup>ND</sup> day of MARCH  
A. D. 1995 at 9:10 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
on page 217.  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Richard L. Drahn, in a field survey on September 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt, U.S. Deputy Surveyor, on September 8, 1847. Original bearing trees:

- |        |    |        |          |              |
|--------|----|--------|----------|--------------|
| B. Ash | 7" | S.38E. | 12 links | ( 7.92 feet) |
| B. Ash | 9" | N.80W. | 7 links  | ( 4.62 feet) |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No G.L.O. remains. Corner position re-established on line between and equal distance from the northwest and southwest section corners of Section 19; T48N., R.44W.



**PEER GROUP APPROVED**  
Richard L. Drahn 3/1/95  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I set a 3/4" x 4 foot solid aluminum marsh rod with a 3 1/4" aluminum cap with magnet, stamped to read: T.48N., R.44-45W.; 1/4; S-19, S-24; 1994; R.L.S. 21564 from which I established the following new blazed and scribed bearing trees and/or objects:

- |     |            |        |            |
|-----|------------|--------|------------|
| 6"  | Cedar      | N.20W. | 21.72 feet |
| 9"  | Cedar      | S.11W. | 12.81 feet |
| 13" | Black Ash  | N.75W. | 16.14 feet |
| 6'  | Steel Rail | N.87E. | 1.28 feet  |

Signed by Richard L. Drahn Date February 6, 1995  
Surveyor's Michigan License No. 21564