

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>45W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>48N</u> R <u>44W</u>	<u>A-11</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's office }
Gogebic County } SA.

Received for record the
21ST day of JULY
A. D. 1999 at 1:25 o'clock
P m., and recorded in
Liber 7 of CORNERS
on page 195
Romona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Section Corner 25, 36, 30 & 31; T.48 N., R.44-45 W.

I, Richard L. Drahn, in a field survey on July 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt on 9/8/1847. Original bearing trees:

Yellow Birch	10"	S.62½° W.	30 links	(19.80')
Lynn	14"	N.55½° E.	36 links	(23.76')

Corner restored by Donald D. Lappala, RLS 12585 on 8/30/72 from the remains of the two original B.T.s. He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees:

Sugar Maple	10"	N.35° W.	12.5'
Sugar Maple	7"	N.35° E.	23.5'
Sugar Maple	6"	S.57° E.	10.0'
Metal sign post	6'	North	3.2'

Corner recorder in Gogebic County USFS Liber, Page M-11 on 12/9/74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the monument as described and the bearing trees as follows:

Sugar Maple	11"	N.37° W.	12.13'	(new nail)
Sugar Maple	10"	N.35° E.	23.32'	(new nail)
Sugar Maple	8"	S.60° E.	10.02'	(new nail)
Steel sign rail	6'	N.02° E.	3.15'	

Fragments of Yellow Birch wood and bark remain from the Yellow Birch B.T.. Only a stump hole remain from the Lynn B.T.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

Sugar Maple	10"	S.39° W.	45.72'
-------------	-----	----------	--------

BEER GROUP APPROVAL
Richard L. Drahn 7/20/99
COUNTY REGISTRAR



Signed by Richard L. Drahn Date July 19, 1999

Surveyor's Michigan License No. 21564