

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 44W B-9

T___ R___

T___ R___ SURVEY &

T___ R___ REMONUMENTATION

2. Property Controlling
in Section

S___ T___ R___

S___ T___ R___ JAN 05 2001

3. Miscellaneous
Property in Sec.

S___ T___ R___

S___ T___ R___

SECTION

Received for record the
26TH day of MAY

A. D. 2000 at 11:10 o'clock

A m., and recorded in

Liber 7 of CORNERS

332

Cheryl Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter corner, Sections 19 & 30, T48N, R44W

I, John P. Goss, in a field survey on April 4, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9	●										
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Maple 10" S 39° W 24 links (15.84 ft.)
Yellow Birch 8" N 51° E 12 links (7.92 ft.)

Donald D. Lappala, 12585, on Sept. 23, 1972, restored corner position at recored bearing and distance from the two original bearing trees. He set a 2" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position. He established the following reference objects: 6" S. Maple - N 78° E - 15.8 ft.; 6" S. Maple - S 35° E - 27.5 ft.; 5" S. Maple - S 58° W - 15.2 ft.; metal sign post - S 18° E - 3.9 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On December 9, 1974, he recorded said corner in U.S.F.S. Liber, Index No. R-3.

Found a large decayed Yellow Birch stump at ground level at N 51° E - 12 links

Found D. Lappala monument and accessories.

Act 74 research on file.

FREE GROUP APPROVED
Richard R. Dealm 05/24/00
COUNTY REGISTER OF DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument stamped to read: T.48 N., R.44 W.; 1/4; S-19, S-30; R.L.S. 12585; 1972, from which I established the following existing and new reference objects:

9" Sugar Maple N 78° E 16.20 ft.
10" Sugar Maple S 35° E 27.51 ft.
8" Sugar Maple S 68° W 15.14 ft.
10" Sugar Maple Due West 44.99 ft.
Metal sign post S 18° E 3.9 ft. to face
(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date April 4, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. R-3