

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey

T48N R44W G-9
T___R___
T___R___ **SURVEY &**
T___R___ **MONUMENTATION**

2. Property Controlling in Section

S___T___R___
S___T___R___ JAN 05 2001

3. Miscellaneous Property in Sec.

S___T___R___
S___T___R___

SECTION

Received for record the
26th day of MAY
A. D. 20 00 at 11:10 o'clock
A m., and recorded in
Liber 7 of CORNERS
Page 334
Cheeryl Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
Section Corner, Sections 19, 20, 29 & 30, T48N, R44W

I, John P. Goss, in a field survey on March 14th 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.
Original bearing trees: Sugar Maple 8" S 150 W 26 links (17.16')
Sugar Maple 8" N 440 E 14 links (9.24')

Donald D. Lappala, 12585, on Aug. 18, 1972, restored corner position at record bearing and distance from the stump holes of the two original bearing trees. He set a 2" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position. He established the following reference objects: 13" S. Maple (now stub) - N 02° W - 28.9'; 13" Elm (now stump) - N 41° E - 12.3'; 8" Y. Birch - S 32° W - 17.5'. He recorded said corner on Dec. 9, 1974 in

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Liber R-5 of USFS Records, in courthouse.
J. Garske, 28410, added the following reference in 1993: 8" S. Maple - N01°W 20.58'; 4" S. Maple - S 64° E - 21.30'.

Found Lappala Monument and Lappala & Garske, accessories.

Act 74 research on file.

DEED CLERK APPROVED
Richard E. Deahn 05/24/00
COUNTY REGISTRAR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From found monument and cap stamped: T.48 N., R.44 W.; S-19, S-20, S-29, S-30;
R.L.S. 12585; 1972; I established the following existing and new reference objects:

12" Yellow Birch	S 30° W	17.48 ft.
10" Sugar Maple	N 01° W	20.58 ft.
6" Sugar Maple	S 64° E	21.30 ft.
9" Maple	N 80° W	26.66 ft.
Metal sign post	N 17° W	2.3 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date March 14, 2000

USFS # R-5