

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

GOGEBIC
(County)

Located In: Corner Code #

1. Public Land Survey

T 48^N R 44^W C-11

2. Property Controlling in Section

S T R SURVEY & MONUMENTATION

3. Miscellaneous Property in Sec.

S T R JAN 05 2001

Received for record the
22ND day of JUNE

A. D. 19 00 at 1:20 o'clock

P m., and recorded in
Liber 8 of CORNERS

Page 2
Cheryl Kipp, Dep
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION

Section Corner, sections 29, 30, 31 & 32, T48N, R44W

I, John P. Goss, in a field survey on May 26, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Yellow Birch 10" S 75° E 10 links (6.60 ft.)
Fir 10" N 81° W 4 links (2.64 ft.)

Donald D. Lappala, 12585, on April 4, 1972, restored corner position at record bearing and distance from decayed remain of Yellow Birch B.T. and natural features and line trees to east and west. He set a 2" by 5" iron pipe with 3" bronze tablet. He established the following references:

4" Sugar Maple - N 62° W - 24.6 ft. 5" Sugar Maple - N 02° E - 22.0 ft.
5" Sugar Maple - N 47° E - 24.0 ft. A metal sign post - N 32° W - 1.7 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On Dec. 9, 1974, recorded said corner in U.S.F.S. Liber, Index V-5.

No original evidence found.

I recovered the monument and accessories as described above.

Act 74 research on file.

FEEB GROUP APPROVED
Richard L. Drahn 6/21/00
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument, I established the following existing and new reference objects:

4" Sugar Maple N 62° W 24.61 ft.
6" Sugar Maple N 02° E 22.08 ft.
11" Sugar Maple N 47° E 24.05 ft.
14" Hemlock S 69° W 27.95 ft.
8" Yellow Birch S 67° E 12.11 ft.
A metal sign post N 32° W 1.70 ft. to face
(All measurement taken to nail in side of tree)



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date May 26, 2000

U.S.F.S. No. V-5