

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
25<sup>th</sup> day of August  
A. D. 2000 at 1:20 o'clock  
P m., and recorded in  
Liber 9 of CORNERS  
no page 14  
Ramona Collins Deputy  
Register of Deeds

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 44W C-12

T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_ **SURVEY &**  
T\_\_\_ R\_\_\_ **MONUMENTATION**

2. Property Controlling  
in Section.

S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

JAN 05 2001

3. Miscellaneous  
Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter corner Sections 31 & 32, T48N, R44W

I, John P. Goss, in a field survey on Aug. 18, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Spruce 14" S 42° W 18 links (11.88 ft.)  
Yellow Birch 6" N 22° E 21 links (13.86 ft.)

Donald D. Lappala, 12585, on Sept. 29, 1972, found corner marked by a 4"x4"x24" wood post at record bearing and distance from the remains of the two original bearing trees. He set a 2" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position. He established the following reference objects:  
10" Cedar - N 65° W - 41.3 ft. 4" Spruce - S 86° E - 19.8 ft.  
7" Tamarack - S 30° W - 24.4 ft. Metal sign post - N 71° E - 2.6 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

He recorded said corner on Dec. 9, 1974, in U.S.F.S. Liber, Index No. X-5.

Found a Large badly decayed Spruce stump at S 42° W - 18 links.

Found Donald D. Lappala monument and accessories.

Act 74 research on file.

**DEED GROUP APPROVED**  
Richard P. Dean 8/23/00  
**COUNTY REGISTER**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From found monument stamped to read: T.48 N., R.44 W., 1/4; S-31, S-32; R.L.S. 12585; 1972, from which I established the following existing and new reference objects:

12" Cedar N 65° W 41.06 ft.  
9" Spruce S 86° E 19.84 ft.  
15" Tamarack S 30° W 24.25 ft.  
6" Cedar N 05° E 34.94 ft.  
Metal sign post N 71° E 2.6 ft. to face

(All measurement taken to nail in side of tree).



Signed by John P. Goss

Date August 18, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. X-5