

**SURVEY &  
REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
Gogebic County } ss.

Received for record the  
9<sup>TH</sup> day of APRIL  
A. D. 1997 at 10:45 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
on page 98  
Richard J. Burton  
Register of Deeds ck

Register of Deeds Stamp & File Number

For corners in  
Gogebic  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>48N</u> R <u>44W</u>	<u>D-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 5 & 8; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on October 28, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3		8	9	10	11	12							
4	7												
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/13/1848. Original B.T.s --- Cedar 20" S.43 W. 20 links (13.20') --- Sugar 12" N.55 E. 35 links (23.10') ---  
Corner restored by Richard L. Drahn, RLS 21564 on 8/15/75 from the remains of the original Sugar BT and from a line tree and natural feature east. He set a 2" dia iron pipe with a 3" stamped brass and the following new B.T.s --- 13" Cedar (13" dead) N.05 W. (N.07 W.) 17.8' (17.86') --- 6' (9") Sugar N.33 W. (N.34 W.) 35.7' (35.73') --- 13" (15") Cedar (leaning) N.71 W. (N.70 W.) 33.2' (32.84') --- 7' Metal sign post N.04 W. (N.03 W.) 18.0' (14.01') --- Corner recorded in Gogebic County in Liber 1, Page 172 on 1/27/76.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.  
Recovered the monument as described and the bearing trees as noted in parentheses above. No evidence remains of the original bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:  
9" Sugar Maple S.79 E. 19.17'

PEER GROUP APPROVED  
Richard L. Drahn 11/11/96  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date November 8, 1996  
Surveyor's Michigan License No. 21564