

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's office }
 Gogebic County } ss.

For corners in

Gogebic

(County)

Located In:

Corner Code #

1. Public Land Survey

T 48 N R 44 W D-11

T ___ R ___
 T ___ R ___ SURVEY &
 T ___ R ___ MONUMENTATION

2. Property Controlling in Section

S ___ T ___ R ___

JAN 05 2001

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

SECTION

Received for record the

22nd day of JUNE

A. D. 19 00 at 1:20 o'clock

P m., and recorded in

Lib 8 of CORNER

on page 3

Cheryl Ruppel, Dep
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter section corner, Sections 29 & 32, T48N, R44W

I, John P. Goss, in a field survey on May 25, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	I
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Hemlock 10" S 25 $\frac{1}{2}$ ° E 21 links (13.86 ft.)
 Hemlock 7" N 30° W 5 links (3.30 ft.)

Donald D. Lappala, 12585, on August 3, 1972, restored corner position at record bearing and distance from the remains of the two original BT's. He set a 2" by 5' iron pipe with 3" bronze tablet. He established the following references.
 8" Hemlock - N 35° E - 23.0 ft.(down) 10" Hemlock - S 01° E - 24.0 ft.
 5" Hemlock - S 73° W - 21.3 ft. metal sign post - S 35° W - 2.7 ft.
 In 1993 J. Garske added 8" Hemlock - N 44° W - 22.95 ft. (out) and

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10" Hemlock - N 35° E - 8.22 ft.

On Dec. 9, 1974, Lappala recorded said corner in U.S.F.S. liber, Index V-7.

Found both original bearing trees now stumps at ground level.

I recovered the monument as set by Lappala and some of the corner's accessories.

Act 74 research on file.

DEED GROUP APPROVED
Richard P. Dahn 6/21/00
 COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument I established the following existing and new reference objects:

11" Hemlock	S 01° E	24.09 ft.
10" Hemlock	N 35° E	8.22 ft.
7" Hemlock	S 73° W	21.33 ft.
7" Maple	S 42° E	8.64 ft.
metal sign post	S 35° W	2.71 ft. to face.

(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date May 25, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. V-7