

**SURVEY &
REMONUMENTATION**

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>47N</u> R <u>44W</u>	<u>D-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>48N</u> R <u>44W</u>	<u>D-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }
Gogebic County } ss.

Received for record the
18th day of August
A. D. 1997 at 11:00 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 184;
Bumona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Cor 5 & 32; T.47-48 N., R.44 W.

I, Richard L. Drahn in a field survey on August 5, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 11, 1847. Original B.T.s --- Cedar (no dia.) N.11 E. 20 links (13.20') --- Y. Birch (no dia.) N.55 W. 20 links (13.20') ---

Corner restored on 8/8/72 by D. Lappala (12585) from the remains of the two original B.T.s. The first was a scribed Cedar windfall and the second was a decayed Y. Birch stump. He set a 2' X 60" iron pipe with a 3" stamped brass cap and the following B.T.s: --- 5" (6") Sugar Maple N.35 W. (N.35 W.) 20.4' (20.19') --- 6" (8") Sugar Maple N.34 E. (N.33 E.) 28.4' (28.09') --- 10" (15") Ash S.55 E. (S.55 E.) 14.4' (14.42') --- Metal sign post N.15 E. (N.18 E.) 2.2' (2.14') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in USFS Liber, Page 2-7, on December 9, 1974.

Recovered the corner as described and the bearing objects as indicated in parentheses above. Portions of the original Cedar still remain. No evidence remains of the original Yellow Birch B.T.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.

7" Yellow Birch S.87 W. 8.61'

PEER GROUP APPROVED

Richard L. Drahn 8/13/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 8, 1997

Surveyor's Michigan License No. 21564