

SURVEY & REMONUMENTATION

AUG 08 1997

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
9TH day of APRIL

A. D. 1997 at 10:45 o'clock

A and recorded in
 Liber 6 of CORNERS

on page 99

Richard J. Brown
 Register of Deeds cc

Register of Deeds Stamp & File Number

For corners in COMMISSION

Gogebic
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>48N</u> R <u>44</u> W | <u>E-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner 8 & 9, T.48 N., R.44 W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5			4			3		2			
3													
4	7	8			9			10		11			12
5													
6	18	17			16			15		14			13
7													
8	19	20			21			22		23			24
9													
10	30	29			28			27		26			25
11													
12	31	32			33			34		35			36
13													

I, Richard L. Drahn in a field survey on October 28, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 6/20/1848. Original B.T.s --- Y. Birch 22" S.35 W. 17 links (11.22') --- Sugar 10" N.24 E. 8 links (5.28') ---
 Corner restored by Richard L. Drahn, RLS 21564 on 6/20/75 from the decayed remains of the two original B.T.s and from line trees and natural features north and south. He set a 2" diameter iron pipe with a 3" stamped brass cap and the following new B.T.s --- 3" (4") Maple (Sugar Maple) N.07 W. (N.08 W.) 12.8' (12.75') --- 4" Maple (dead and down) N.85 E. (N.86 E.) 31.1' --- 6" Maple (dead Sugar Maple stub) S.13 E. (S.14 E.) 24.2' (24.24') --- 7' Metal sign post (now Down) East 3.4' (S.87 E. 3.3') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 1, Page 171 on 1/27/76.

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. Stump holes still remain from the two original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees referenced:

- 17" Sugar Maple S.08 E. 28.49'
- 14" Sugar Maple N.88 E. 17.78'

PEER GROUP APPROVED
Richard L. Drahn 11/11/96
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date November 8, 1996

Surveyor's Michigan License No. 21564