

**SURVEY &
REMONUMENTATION**

AUG 08 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Gogebic
(County)

Located In:

Corner Code ##

- | | | | | | |
|---------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>48N</u> | R | <u>44W</u> | <u>E-5</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling
in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 8, 9, 16 & 17; T.48 N., R.44 W.

Richard L. Drahn in a field survey on October 28, _____, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 6/20/1848. Original B.T.s --- Fir 7" S.52 E. 4 links (2.64') --- B. Ash 7" N.52 W. 9 links (5.94') ---

Corner restored by Richard L. Drahn, RLS 21564 on 6/20/75 from the remains of the B. Ash B.T. and from line trees north and east and from natural features east, west and south. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: 3" (4") Maple (Sugar) N.35 W.27.2' (N.34 W. 27.54') --- 4" Maple (7" Sugar) N.25 E. 26.2' (N.25 E. 26.23') --- 6" Maple (8" Sugar) N.68 E. 14.9' (N.66 E. 15.07') --- &' Metal sign post N.38 E. 3.7' (N.40 E. 3.52') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 1, Page 170 on 1/27/76.

Act 74 research form on file with Gogebic County records.

Recover the monument as described and the bearing trees as noted in parentheses above.

No evidence remains of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

7" Black Ash S.22 E. 3.72'

PEER GROUP APPROVED
Richard L. Drahn 11/11/96
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date November 8, 1996

Surveyor's Michigan License No. 21564

Register of Deeds Stamp & File Number

Register's Office }
Gogebic County } ss.

Received for record the
9th day of APRIL

A. D. 1997 at 10:45 o'clock

A m., and recorded in
Liber 6 of CORNERS

on page 100

Richard J. Brown
Register of Deeds ck

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													