

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Saginaw County } ss.

Received for record this
26th day of MAY
A. D. 1900 at 11:10 o'clock
4 m., and recorded in
Liber 7 of CORNELLS
page 337
Abner Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC
(County)

Located In:

Corner Code #

1. Public Land Survey

T48N R44W E-7

2. Property Controlling
in Section

S T R
S T R

**SURVEY &
MONUMENTATION**

3. Miscellaneous
Property in Sec.

S T R
S T R

JAN 05 2001

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner, Sections 16, 17, 20 & 21, T48N, R44W

I, John P. Goss, in a field survey on March 31st 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.
Original bearing trees: Spruce 15" S 15° E 19 links (12.54 ft.)
Hemlock 14" N 41° W 43 links (28.38 ft.)

Donald D. Lappala, 12585, on August 20, 1968, restored corner position from the original bearing trees. He set a 2" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position. He established the following reference objects: 6" Y. Birch - N 30° W - 18.3 ft.; 7" W. Spruce - N 84° E - 24.6 ft.; 13" Hemlock - S 02° W - 26.0 ft.; in 1989 P.S. & J.D. added a 4"x4" wood post N 15° E - 3.7 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
He recorded said corner in U.S.F.S. Liber on page N-9 on March 31, 1969.

Found Lappala monument and accessories. Also found original bearing tree now a badly decayed hemlock stump.

Act 74 research on file.

NEED GROUP APPROVED
Richard L. Dean 05/12/00
COUNTY REGISTRAR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
From the found monument stamped to read: T.48 N., R.44 W.; S-16, S-17, S-20, S-21; R.L.S. 12585; 1968, from which I established the following existing and new reference objects:

- 12" Yellow Birch N 30° W 18.26 ft.
- 13" White Spruce N 84° E 24.67 ft.
- 16" Hemlock S 02° W 26.14 ft.
- 4"x4" Wood post & sign N 15° E 3.7 ft. to face
- 6' rail & sign N 70° W 0.95 ft. to face

(All measurement taken to nail in side of tree)



Signed by John P. Goss

Date March 31, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. N-9