

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County }

Received for record this

26<sup>th</sup> day of MAY

A. D. 19 00 at 11:0 o'clock

A. M., and recorded in

Lib. 7 of COLBERS

at page 338

*Cheryl Rippe*  
Dep. Register of Deeds

Register of Deeds Stamp & File Number

For corners in

GOGEBIC

(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 44W E-8

T R

T R SURVEY &

T R REMONUMENTATION

2. Property Controlling  
in Section

S T R JAN 05 2001

3. Miscellaneous  
Property in Sec.

S T R

S T R

SECTION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Quarter corner, Sections 20 & 21, T48N, R44W

I, John P. Goss, in a field survey on April 7, 19 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Hemlock 16" S 28° W 10 links (6.60 ft.)  
Sugar Maple 12" N 21° E 33 links (21.78 ft.)

Donald D. Lappala, 12585, established the quarter corner by single proportional measurement between the recovered section corners 1/2 mile to the North & South. He set a 5/8" dia. by 14" long iron pin. He established the following reference objects: At 23.57 ft. West of corner he set a 2 1/2" I.D. iron pipe with 3" bronze cap, stamped to indicated corner position; 3" S. Maple - N 78° W - 78.1 ft. 5" S. Maple - S 74° W - 87.2 ft.; 7" S. Maple - S 86° W - 83.9 ft.; metal sign

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: On Dec. 9, 1974, Lappala recorded said corner in U.S.F.S. Liber, Index No. P-9.

Found Lappala monument and accessories.

Act 74 research on file.

Lappala established quarter corner on August 18, 1972.

*Richard P. Dealan* 05/24/00  
COURT 23509/14719

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3" below surface I place a 3 1/4" aluminum cap over the 5/8" iron pin, cap stamped to read: County Remonumentation; T.48 N., R.44 W., 1/4; S-20, S-21; 2000, P.S. 23509. From which I established the following existing and new reference object

Reference Monument	West	23.57 ft.
3" Sugar Maple	N. 78° W	78.1 ft. stub
8" Sugar Maple	S 74° W	87.30 ft.
9" Sugar Maple	S 86° W	84.25 ft.
7" Aspen	S 82° E	41.88 ft.
Metal sign post	West	26.5 ft. to face

(All measurement taken to nail in side of tree)

Signed by John P. Goss

Date April 7, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. P-9

