

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Received for record the
26TH day of MAY
A. D. 19 at 11:10 o'clock
A m., and recorded in
Liber 7 of CORNERS
page 339
Robert Ruppe
Dep. Register of Deeds

Register of Deeds Stamp & File Number

GOGEBIC Located in: Corner Code #
(County)

1. Public Land Survey T48N R 44W E-9
T R
T R
T R SURVEY &
2. Property Controlling S T R REMONUMENTATION
in Section S T R
3. Miscellaneous S T R JAN 05 2001
Property in Sec. S T R

SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
Section Corner, Sections 20, 21, 28 & 29, T48N, R44W

I, John P. Goss, in a field survey on April 6, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.
Original bearing trees: Yellow Birch 8" S 41° E 18 links (11.88 ft.)
Yellow Birch 16" N 66° W 17 links (11.22 ft.)

Donald D. Lappala, 12585, on Aug. 11, 1972, restored corner by reference post and a stream call, a cedar and yellow birch line trees East of corner also a very old brazed line east and west from corner. He set a 5/8" dia. by 15" long iron pin. He established the following reference objects: At 29.95 ft. West of corner he set a 2" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position; 7" Ash - N 55° W - 84.5 ft. (now stub); 9" S. Maple -

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

S 70° W - 83.3 ft.; Power Pole #176 - N 19° W - 66.5 ft. (now out); a metal sign post - N85° W - 30.0 ft.; in 1986 J. Garske added a P.Pole #168 - N22°W- 78.25
On Dec. 9, 1974, Lappala recorded said corner in U.S.F.S. Liber, Index No. R-9.

Found Donald Lappala monument and accessories.

Act 74 research on file.

Richard P. Drah 05/24/00
COUNTY CLERK GOGEBIC COUNTY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 5/8" by 15" bended iron pin with a 5/8" by 20" rebar with a 3/4" aluminum cap, 5" below surface, stamped to read: T48N, R44W; S-20, S-21, S-28, S-29, P.S. 23509; 2000; County Remonumentation. I established the following existing and new reference objects:

10" Sugar Maple	S 70° W	83.40 ft.
Power Pole #168	N 22° W	78.21 ft. new nail
6" Maple	N 57° E	39.84 ft.
Reference Monument	West	29.95 ft.
Metal sign post	N 85° W	30.0 ft. to face

(All measurement taken to nail in side of object)

1" iron pipe in roadway S 05° E - 7.45 ft. from corner.

Signed by John P. Goss

Date April 7, 2000

Surveyor's Michigan License No. 23509

U.S.F.S. No. R-9

