

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

GOGEBIC
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------|------------------------|
| 1. Public Land Survey | T <u>48</u> N R <u>44</u> W | E-10 |
| | T ___ R ___ | |
| | T ___ R ___ | SURVEY & |
| | T ___ R ___ | REMONUMENTATION |
| 2. Property Controlling in Section | S ___ T ___ R ___ | |
| | S ___ T ___ R ___ | JAN 05 2001 |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | |
| | S ___ T ___ R ___ | SECTION |

Received for record the
26th day of MAY
A. D. 2000 at 11:20 o'clock
A m., and recorded in
Liber 7 of CORNERS
on page 340
Cheryl Rippe
Reg. Registrar of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner, Sections 28 & 29, T48N, R44W

I, John P. Goss, in a field survey on April 7, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.
Original bearing trees: Hemlock 6" S 54° E 5 links (3.30 ft.)
Sugar Maple 12" N 35° W 24 links (15.84 ft.)

Donald D. Lappala, 12585, on August 18, 1972, restored quarter corner by single proportionate measurement in the centerline of Old M-28 between section corners 1/2 mile North and South. He set a 5/8" dia. by 14" long, iron pin. He established the following reference objects: At 24.00 feet West of corner he set a 2 1/2" I.D. iron pipe with 3" bronze tablet, stamped to indicated the corner position. 6" Elm - N78°E - 37.3 ft. dead; 10" Elm - S45°E - 54.2 ft. dead; P.P. #167

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: M.S.P.-N82°W-22.2 ft. N79°W - 24.6 ft. cut down; in 1986 the following were added: 18"W.Pine-N66°W 85.20 ft.; 9"R.Maple - S61°W - 96.95 ft.; P.P.#159 - N63°W - 36.42 ft. On December 9, 1974, Lappala recorded said corner in U.S.F.S. Liber, Index #T-

Found Lappala monument and accessories and the added accessories.


Act 74 research on file.

Richard P. Deahn 05/24/00
COUNTY GOGEBIC REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2" below surface I placed a 3 1/4" aluminum cap over the 5/8" iron pin, cap stamped to read: County Remonumentation; T.48 N., R.44 W., 1/4; S-28, S-29, 2000, P.S. 23509. From which I established the following existing and new reference objects:

Reference Monument	West	24.00 ft.
24" White Pine	N 66° W	85.52 ft.
11" Red Maple	S 61° W	97.25 ft.
Power Pole #159	N 63° W	36.28 ft.
Metal sign post	N 82° W	22.2 ft. to face
(All measurement taken to new nail in side of object)		



Signed by John P. Goss
Surveyor's Michigan License No. 23509

Date April 7, 2000

U.S.F.S. No. T-9