

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

|                                    |                           |               |
|------------------------------------|---------------------------|---------------|
| <u>Gogebic</u><br>(County)         | Located In:               | Corner Code # |
| 1. Public Land Survey              | T <u>47N</u> R <u>44W</u> | <u>E-1</u>    |
|                                    | T _____ R _____           | _____         |
|                                    | T _____ R _____           | _____         |
|                                    | T <u>48N</u> R <u>44W</u> | <u>E-13</u>   |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____         |
|                                    | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                    | S _____ T _____ R _____   | _____         |

Received for record the  
18<sup>TH</sup> day of AUGUST  
A. D. 1997 at 11:00 o'clock  
A m., and recorded in  
Liber 6 of CORNERS  
page 187  
Ramona Collins, Deputy  
Register of Deeds  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Sec. Cor. 4, 5, 32 & 33; T.47-48 N., R.44 W.

I, Richard L. Drahn in a field survey on August 6, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  |    |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
Corner established by Austin Burt on August 11, 1847. Original B.T.s ---  
B. Ash 6" N.25 E. (no dist.) --- Hemlock 18" N.73 W. (no dist.) --- Hemlock 20" S.35 E. 40 lks. (26.40') --- W. Pine 30" S.60 W. 28 lks. (18.48') ---

Corner restored on 8/1/72 by D. Lappala (12585) from the remains of the third B.T. and the decayed W. Pine stump with GLO B.T. blaze. He set a 2" X .60" iron pipe with a 3" stamped brass cap and the following new B.T.s:  
--- 10" (12") Ash N.65 W. (N.65 W.) 27.7' (27.63') --- 5" (6" near dead) Ash East(S.83 E.) 20.2' (20.25') --- 5" (11") Sugar Maple S.36 E. (S.33 E.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
36.1' (35.99') --- Metal sign post N.55 E. (N.35 W.) 1.1' (1.20'). ---  
Corner recorded in USFS Liber, Page Z-9 on 12/9/74.

Recovered the corner as described and the bearing objects as indicated in parentheses above. Only a large decayed W. Pine stump remains of the original B.T.s.  
Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
From the above described monument I established the following new B.T.:  
8" Black Ash N.12 E. 20.60'

PEER GROUP APPROVED  
Richard L. Drahn 8/13/97  
COURT REPRESENTATIVE



Signed by Richard L. Drahn Date August 8, 1997

Surveyor's Michigan License No. 21564  
USFS A-9  
Z-9