

SURVEY & REMONUMENTATION

JAN 22 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
24TH day of NOVEMBER
A. D. 1997 at 11:40 o'clock
A m., and recorded in
Liber 6 of CORNERS
page 273
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 4 & 9; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on November 8, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on September 11, 1848. Original B.T.s --- 12" Y. Birch S.53 W. 22 links (14.52') --- 16" Y. Birch N.57 $\frac{1}{2}$ E. 50 links (33.00') ---

Corner restored on 11/7/74 by Richard L. Drahn (21564) from the remains of the two original B.T.s. He set a 2 $\frac{1}{2}$ " X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s: 7" (8") Sugar Maple N.03 W.(N.01 E.) 23.6' (23.64') --- 6" (7") Sugar Maple S.84 W. (S.85 W.) 15.5' (15.48') --- 9" (11") Sugar Maple S.47 E. (S.44 E.) 7.2' (7.28') --- 4" X 4" X 7' Cedar sign post North (N.17 E.) 3.3' (3.16') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Gogebic County in Liber 1, Page 293 on 3/7/77.

Research form on file with Gogebic County records.

Recovered the corner as described and the bearing objects as indicated in parentheses above. Stump holes are all that remain of the two original Bearing Trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following:

6' Steel sign rail S.59 W. 2.61'

PEER GROUP APPROVED

Richard P. Drahn 11/11/97
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date November 9, 1997

Surveyor's Michigan License No. 21564