

**SURVEY & REMONUMENTATION**

OCT 0 8 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |                              |            |
|------------------------------------|------------------------------|------------|
| 1. Public Land Survey              | T <u>48</u> N R <u>44</u> W. | <u>F-5</u> |
|                                    | T _____ R _____              | _____      |
|                                    | T _____ R _____              | _____      |
|                                    | T _____ R _____              | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____      | _____      |
|                                    | S _____ T _____ R _____      | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____      | _____      |
|                                    | S _____ T _____ R _____      | _____      |

Register's Office }  
Gogebic County } ss.

Received for record the  
23<sup>RD</sup> day of FEB  
A. D. 1996 at 1:35 o'clock  
P m., and recorded in  
Liber 5 of CORNERS  
on page 320  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 9 & 16; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on November 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5						●							
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/11/1848. Original B.T.s --- Sugar Maple 8" S.36 W. 29 links (19.14') --- Lynn 8" N.50 E. 32 links (21.12').

Corner restored by Richard L. Drahn, RLS 21564 on 6/20/75 from the remains of the two original B.T.s and from recovered line trees east and west. He set a 2" x 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees: --- 7" (8") Sugar Maple N.62 E. (N.60 E.) 18.2' (18.28') --- 7" (10") Sugar Maple (White Ash) S.41 E. (S.39 E.) 26.0' (26.22') --- 6" (7") Sugar Maple S.21 W. ( S.22 W.) 32.4' (32.51') --- 7' Metal sign post North (N2W) 3.0' (3.0')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

New bearing tree referenced;

9" White Ash N.30 W. 18.67'

Resource grade GPS

Lat. 46 - 33.762 N.  
Long. 89 - 48.850 W.

Recovered the monument as described and the bearing trees as noted in parentheses above. No evidence remains of the GLO B.T.s.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner recorded in Gogebic County in Liber 1, Page 169 on 1/27/76.

Act 74 research form on file with Gogebic County records.

PEER GROUP APPROVED

Richard L. Drahn 12/14/95  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date December 12, 1995

Surveyor's Michigan License No. 21564