

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

GOGEBIC  
(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 44W

F-9

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

**SURVEY &  
MONUMENTATION**

**JAN 05 2001**

**SECTION**

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_  
Quarter section, Sections 21 & 28, T48N, R44W

I, John P. Goss, in a field survey on June 5, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Cedar 14" S 62° E 45 links (29.70 ft.)  
Yellow Birch 11" N 30° W 29 links (19.14 ft.)

Donald D. Lappala, 12585, on Sept. 4, 1968, restored corner position at record bearing and distance from the remains of the original bearing trees. The scribed cedar windfall and a large decayed yellow birch stump hole. He set a 2" by 5" iron pipe with 3" bronze tablet. He established the following reference:  
13" Yellow Birch N 06° W 28.6 ft.; 7" Sugar Maple S 88° E 8.5 ft.;  
7" Sugar Maple S 85° W 19.0 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On March 31, 1969, he recorded said corner in U.S.F.S. Liber, Index R-11

Found the first original bearing tree, now a windfall 23" scribed cedar.

I recovered the monument and accessories as described above.

Act 74 research on file.

**DEED GROUP APPROVED**  
Richard L. Deal - 6/2/00  
**COURT RECORDED**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the found monument, I established the following existing and new reference objects:

16" Yellow birch N 04° W 28.61 ft.  
12" Sugar Maple S 84° E 8.68 ft.  
12" Sugar Maple S 85° W 18.78 ft.  
6" Rail & sign S 06° E 2,11 ft. to face  
(All measurements taken to nail in side of tree)



Signed by John P. Goss

Surveyor's Michigan License No. 23509

U.S.F.S. No. R-11

Date June 5, 2000