

NOV 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in

Gogebic <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 47N R 44W	F-1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Received for record the  
18<sup>th</sup> day of AUGUST  
 A. D. 1997 at 11:00 o'clock  
A m., and recorded in  
 Liber 6 of CORNERS  
 on page 189  
Ramona Collins, Deputy  
 Register of Deeds  
 Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1/4 Corner 4 & 33; T.47-48 N., R.44 W.

I, Richard L. Drahn in a field survey on August 6, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 11, 1847. Original B.T.s ---  
 Y. Birch 24" N.71 E. 16 links (10.56') --- Hemlock 24" N.17 W. 29 links (19.14')

Corner restored on 10/2/72 by D. Lappala (12585) from the remains of the Y. Birch B.T., the stump hole of the Hemlock and from recovered line trees and natural features west. He set a 2" X 60" iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 10" (15") Sugar Maple N.15 E. (N.16 E.) 32.1' (32.08') --- 8" (12") Sugar Maple S.02 W. (S.05 W.) 24.6' (24.42') --- 10" (14") Sugar Maple S.73 W. (S.75 W.) 24.4' (24.08') --- Metal sign post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

S.24 W. (S.24 W.) 2.9' (2.90')---

Corner recorded in USFS liber, page Z-11 on 12/9/74.

Recovered the corner as described and the bearing objects as indicated in parentheses above. Only stump holes remain of the two original B.T.s.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following new B.T.

8" Sugar Maple S.66 E. 9.83'

GROUP APPROVED  
Richard L. Drahn 8/13/97  
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date August 8, 1997

Surveyor's Michigan License No. 21564

USFS A-11  
7-11