

**SURVEY &  
REMONUMENTATION**

OCT 0 8 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                    |   |     |   |    |   |     |
|------------------------------------|---|-----|---|----|---|-----|
| 1. Public Land Survey              | T | 48N | R | 44 | W | G-4 |
|                                    | T |     | R |    |   |     |
|                                    | T |     | R |    |   |     |
|                                    | T |     | R |    |   |     |
| 2. Property Controlling in Section | S |     | T |    | R |     |
|                                    | S |     | T |    | R |     |
| 3. Miscellaneous Property in Sec.  | S |     | T |    | R |     |
|                                    | S |     | T |    | R |     |

Register's Office }  
Gogebic County } SS.

Received for record the  
23<sup>RD</sup> day of FEB.  
A. D. 1996 at 1:35 o'clock  
P.m., and recorded in  
Liber 5 of CORNERS  
on page 318  
*Ramona Collins Deputy*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 9 & 10; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on November 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/8/1848. Original B.T.s --- Sugar Maple 12" S.33 W. 14 links (9.24') --- Sugar Maple 20" N.11 E. 19 links (12.54').

John Meredith, on 4/29/35 recovered the SW BT still scribed and placed a metal location poster on the B.T.

Corner restored by Richard L. Drahn, RLS 21564 on 11/7/74 from the remains of the two original B.T.s, one with Merediths' tag still attached. He set a 2 1/2" X 5' iron pipe monument with a stamped brass cap and the following new bearing objects: --- 8" (9") Sugar Maple N.28 W. (N.26 W.) 23.0' (23.02') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4" Sugar Maple (dead and down) N.77 E. 25.5' --- 7" (9") Sugar Maple S.79 W. (S.82 W.) 15.5' (15.40') --- 4"x4"x7' Cedar sign post South (S.05 W.) 3.4' (3.3').

Recovered the monument as described and the bearing trees as noted in parentheses above. Only a stump hole from the SW original B.T. remains.

Corner recorded in Gogebic County in Liber 1, Page 294 on 3/7/77.

Act 74 research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- |    |                 |         |        |
|----|-----------------|---------|--------|
| 4" | Sugar Maple     | S.52 E. | 14.42' |
| 6' | Steel sign rail | S.71 E. | 1.9'   |

PEER GROUP APPROVED  
*Richard L. Drahn* 12/14/95  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date December 12, 1995  
Surveyor's Michigan License No. 21564