

**SURVEY &
MONUMENTATION**

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the

23RD day of FEB.

A. D. 1996 at 1:35 o'clock

P m., and recorded in

Liber 5 of CORNERS

on page 321.

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44</u> W.	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 9, 10, 15 & 16; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on November 15, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on 9/8/1848. Original B.T.s --- Sugar Maple 8" S.06 W. 10 links (6.60') --- Sugar Maple 8" N.62 E. 07 links (4.62').

Corner restored by Donald D. Lappala, RLS 12585 on 6/28/74 from the remains of the two original B.T.s and from records of L. W. Smith who on 1/12/34 recovered a GLO witness tree at this location. Mr. Lappala set a 2½" by 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees: --- 6" (7") Red Maple N.43 E. (N.42 E.) 9.5' (9.48") --- 9" (12") Sugar Maple N.59 W. (N.59 W.) 19.7' (19.65') --- 6" (8") Sugar Maple S.50 W. (S.49 W.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

49.6' (49.53')

Corner recorded in Gogebic County in USFS Liber, Page J-13 on 3/4/75.

Act 74 research form of file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. A decayed Y. Birch stump still remains from the GLO witness tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

4"x4"x7' Cedar sign post N01 E. 2.4'

6' Steel sign rail S.24 E. 1.15'

PEER GROUP APPROVED
Richard L. Drahn 12/14/95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date December 12, 1995

Surveyor's Michigan License No. 21564