

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } **SL**

Received for record the  
22<sup>ND</sup> day of June  
A. D. 2000 at 1:25 o'clock  
P m., and recorded in  
Liber 8 of CORNERS  
on page 7  
*Cheryl Ruppel*  
Register of Deeds

For corners in

GOGEBIC  
(County)

Located in:

Corner Code #

1. Public Land Survey

T48NR 44W G-11

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

T\_\_\_ R\_\_\_

2. Property Controlling in Section

S\_\_\_ T\_\_\_ R\_\_\_

S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_

S\_\_\_ T\_\_\_ R\_\_\_

**SURVEY &  
MONUMENTATION**

**JAN 05 2001**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**SECTION**

Section Corner, sections 27, 28, 33 & 34, T48N, R44W

I, John P. Goss, in a field survey on June 12, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, in 1848.

Original bearing trees: Yellow Birch 10" S 62° W 40 links (26.40 ft.)  
Cedar 10" N 46° E 6 links (3.96 ft.)

Donald D. Lappala, 12585, on Sept. 5, 1972, restored corner position at record bearing and distance from the decayed remains of the two original bearing trees. Corner position verified further by retracement measurement of sectionlines south, east, and west from corner to recoverable record natural features. He set a 2" by 5" iron pipe with 3" bronze tablet. He established the following references objects:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

8" Sugar Maple N 62° W 41.8 ft.; 6" Sugar Maple N 02° W 17.8 ft.  
9" Cedar S 53° E 29.8 ft.; A metal sign post N 35° W 2.4 ft.  
On December 9, 1974, he recorded said corner in U.S.F.S. Liber, Index V-13.

I recovered the monument and accessories as described above.

Act 74 research on file.

**DEED GROUP APPROVED**  
*Richard L. Deane 6/21/00*  
COUNTY REGISTER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

From the found monument I established the following existing and new reference objects:

8" Sugar Maple N 62° W 41.81 ft.  
7" Sugar Maple N 02° W 17.75 ft.  
12" Cedar S 53° E 29.74 ft.  
11" Hemlock S 53° W 5.93 ft.  
A metal sign post N 35° W 2.40 ft. to face  
(All measurements taken to nail in side of tree)



Signed by John P. Goss  
Surveyor's Michigan License No. 23509

Date June 12, 2000

U.S.F.S. No. V-13