

**SURVEY & REMONUMENTATION**

JAN 22 1998

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44W</u>	<u>H-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register's Office }  
Gogebic County } ss.

Received for record the  
2<sup>ND</sup> day of DECEMBER  
A. D. 1997 at 10:35 o'clock  
A m., and recorded in  
Liber 6 of GORNES  
on page 284  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 3 & 10; T.48N., R.44 W.

I, Richard L. Drahn in a field survey on November 14, 1997, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on September 8, 1848. Original B.T.s --- Y. Birch 12" S.38 $\frac{1}{2}$  E. 39 links (25.74') --- Sugar 22" N.37 W. 19 links (12.54')

Corner restored on 8/13/68 by Donald D. Lappala (12585) from the remains of the two original B.T.s, record natural features and line trees. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s:

- 11" Sugar Maple N.31 W. 27.0'
- 7" Sugar Maple S.14 W. 16.0'
- 8" Sugar Maple S.60 W. 24.7'

Corner recorded in USFS Liber, page E-15 on 3/31/69.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner found marked by the monument as described above and the following B.T.s by Mr. Lappala:

- 16" Sugar Maple N.31 W. 26.76'
- 11" Sugar Maple S.15 W. 15.86'
- 10" Sugar Maple S.60 W. 24.95'

No evidence remains of the original B.T.s except stump holes.

Research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I referenced the following:

- 4" X 4" Cedar sign post S.03 W. 2.19'
- 6' Steel sign post N.03 W. 2.92'

PEER GROUP APPROVED

Richard L. Drahn 12/1/97  
COUNTY REGISTER



Signed by Richard L. Drahn Date November 25, 1997

Surveyor's Michigan License No. 21564

USFS E/15