

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

For corners in

| Gogebic (County) | Located In: | Corner Code # |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T 48N R 44 W | H-5 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Received for record the
23RD day of Feb
 A. D. 1996 at 1:35 o'clock
P m., and recorded in
 Liber 5 of CORNERS
 on page 322.

Ramona Collins Deputy
 Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner 10 & 15; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on November 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | ● | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by Austin Burt on 9/8/1848. Original B.T.s --- Yellow Birch 24" S.18 W. 44 links (29.04') --- Sugar Maple 9" N.88 E. 8 links (5.28')

Corner restored by Richard L. Drahn, RLS 21564 on 11/7/74 from the stump remains of the two original B.T.s. He set a 2 1/2" x 5' iron pipe monument with a stamped brass cap and the following new bearing objects: --- 6" (7") Red Maple N.68 W. (N.66 W.) 35.1' (35.15') --- 6" (9") Sugar Maple N.29 W. (N.27 W.) 42.5" (42.42') --- 7" (9") Sugar Maple N.11 E. (N.12 E.) 35.5' (35.35') --- 4"x4"x7' Cedar sign post North (N.04 E.) 3.9' (3.8').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Recovered the monument as described and the bearing trees as noted in parentheses above. Only a stump hole from the Y. Birch original B.T. remains.

Corner recorded in Gogebic County in Liber 1, Page 296 on 3/7/77.

Act 74 research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 New bearing object referenced:

6' Steel sign rail S.54 W. 2.3 ft.

Resource grade GPS

Lat. 46 - 33.820 N.
 Long. 89 - 47.551 W.

PEER GROUP APPROVED
Richard P. Drahn 12/14/95
 COUNTY REPRESENTATIVE



Signed by Richard P. Drahn Date December 12, 1995
 Surveyor's Michigan License No. 21564