

**SURVEY &
MONUMENTATION**

OCT 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
10th day of JUNE
A. D. 1996 at 11:00 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 392
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{2}$ Corner 22 & 27; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on May 28, 19 96
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on September 7, 1848. Original B.T.s ---
Sugar 8" S.34 E. 13 links (8.58') --- Sugar 6" N.87 W. 29 links (19.14')---
Corner restored by Donald D. Lappala, RLS 12585 on 9/6/72 from the live
B.T. at S.34 E. and the stump hole of the second B.T. He set a 2" dia.
iron pipe with a 3" stamped brass cap and the following new bearing trees:
--- 3" (5") Sugar Maple N.08 E. (N.07 E.) 9.7' (9.59') --- 10" (13") Yellow
Birch S.16 E. (S.13 E.) 54.2' (54.08') --- 6" (9") Sugar Maple S.89 W.
(N.86 W.) 25.1' (25.02') --- Metal sign post N.22 W. (N.19 W.) 2.2' (2.2')---
Corner recorded in Gogebic County in USFS Liber, Page R-15 on 12/9/74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in
parentheses above. The first original B.T. is now a live 27" Sugar Maple
with GLO blazes. Only a depression remains from the second GLO B.T.

PEER GROUP APPROVED

Richard L. Drahn 6/6/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

7" Hemlock S.32 W. 31.23'



Signed by Richard L. Drahn

Date May 30, 1996

Surveyor's Michigan License No. 21564