

SURVEY & REMONUMENTATION

OCT 03 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic
(County)

Located In: Corner Code #/

1. Public Land Survey

		<u>T 48N</u>	<u>R 44W.</u>		<u>H-13</u>
		T	R		
		T	R		
		<u>T 47N</u>	<u>R 44W</u>		<u>H-1</u>
		T	R		
2. Property Controlling in Section

	<u>S</u>	<u>T</u>	<u>R</u>		
	S	T	R		
3. Miscellaneous Property in Sec.

	<u>S</u>	<u>T</u>	<u>R</u>		
	S	T	R		
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 34 & 3; T.48-47N., R.44 W.

I, Richard L. Drahn in a field survey on June 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 11, 1847. Original B.T.s --- Sugar 24" N.45 E. 24 links (15.84') --- Sugar 14" N.46 W. 30 links (19.80') --- Corner restored by Donald D. Lappala, RLS 12585 on 9/14/72 from the remains of the two original bearing trees and from natural feature ties and line trees east and west. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new bearing objects: --- 11" Elm (dead and down) N.88 W. 11.3' --- 7" Elm (dead and down) N.63 E. 15.6' --- 5" Elm (dead and down) S.10 E. 24.0' ---
Corner recorded in Gogebic County in USFS Liber, Page Z-15 (T.48 N.).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.
Recovered the monument as described and the bearing trees as noted in parentheses above.
Stump holes are all that remain of the original bearing tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- | | | |
|-----------------|---------|--------|
| Metal sign post | N.07 W. | 2.7' |
| 8" Sugar Maple | N.35 W. | 8.81' |
| 10" Sugar Maple | N.56 E. | 28.10' |
| 12" Sugar Maple | S.43 E. | 37.52' |

Register's Office }
Gogebic County } ss.

Received for record the
10TH day of JUNE
A. D. 19 96 at 11:00 o'clock
A m., and recorded in
Liber 5 of CORNERS
on page 394
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

PEER GROUP APPROVED
Richard L. Drahn 6/6/96
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date June 2, 1996
Surveyor's Michigan License No. 21564