

**SURVEY & REMONUMENTATION**

OCT 0 3 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

For corners in **COMMISSION**

Received for record the  
23<sup>RD</sup> day of FEB.  
A. D. 1996 at 1:35 o'clock  
P. m., and recorded in  
Liber 5 of CORNERS  
on page 319  
Ramona Collins Deputy  
Register of Deeds

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44</u> W.	<u>I-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{2}$  Corner 10 & 11; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on November 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt in 1848. Original B.T.s --- Hemlock 12" S.12 E. 53 links (34.98') --- Hemlock 12" N. 68 W. 31 links (20.46').

Corner restored by Donald D. Lappala, RLS 12585 on 8/13/68 from the stump remains of the two original B.T.s, one still scribed. He set a 2" x 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees: --- 3" (5") Sugar Maple N.61 W. (N.61 W.) 3.4' (3.35') --- 4" Sugar Maple (dead and down) S.24 E. 31.4' --- 5" Sugar Maple (now dead) S.44 W. 57.7'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Recovered the monument as described and the bearing trees as noted in parentheses above. The original NW B.T. is now a decayed Hemlock stump.

Corner recorded in Gogebic County in USFS Liber, Page G-17 on 3/31/69.

Act 74 research form on file with Gogebic County records.

Resource grade GPS

Lat 46 - 34.245 N.  
Long. 89 - 46.913 W.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing objects referenced:

- 13" Sugar Maple S.10 W. 15.95'
- 11" Sugar Maple S.72 E. 32.65'
- 6' Steel Sign Rail S.30 E. 2.25'
- 7' 4"x4"x7' Downed wood sign post bears S.82 W., 2.5'



PEER GROUP APPROVAL

Richard L. Drahn 12/14/95  
COUNTY REPRESENTATIVE

Signed by Richard L. Drahn Date December 12, 1995  
Surveyor's Michigan License No. 21564