

SURVEY & RE-MONUMENTATION

OCT 03 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

COMMISSION
For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 44 W.	I-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Received for record the
23RD day of FEB.
A. D. 1996 at 1:35 o'clock
P m., and recorded in
Liber 5 of CORNERS
page 323
Ramona Collins, Deputy
Register of Deeds
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 10, 11, 14 & 15; T.48 N., R.44 W.

Richard L. Drahn in a field survey on November 17, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt in 1848. Original B.T.s --- Yellow Birch 20" S.09 E. 28 links (18.48') --- Yellow Birch 18" N.43 W. 4 links (2.64').

Corner restored by Donald D. Lappala, RLS 12585 on 8/13/68 from the scribed remains of the two original bearing trees. He set a 2" x 5' iron pipe monument with a 3" stamped brass cap and the following new bearing trees: --- 7' Cedar (now dead and down) N.24 W. 47.7' --- 12" (15") Cedar N.49 E. (N.51 E.) 38.4' (38.44') --- 6" (9") Hemlock N.84 W. (N.83 W.) 23.7' (23.55').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as noted in parentheses above. The original SE bearing tree is now a decayed Yellow Birch stump. Fragments of Y. Birch bark remain from the NW original B.T.

Corner recorded in Gogebic County in Liber USFS, Page I-5, 3/31/69.

Act 74 research form on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

8" Red Maple S.20 E. 8.56'
6' Steel sign rail S.41 W. 2.15'

Resource grade GPS

Lat. 46 - 33.892 N.
Long. 89 - 46.938 W.

PEER GROUP APPROVED
Richard L. Drahn 12/14/95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date December 12, 1995
Surveyor's Michigan License No. 21564