

MAY 1 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
17th day of OCTOBER
A. D. 1996 at 9:50 o'clock
A m., and recorded in
Liber 6 of CORNERS

on page 66
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Table with 3 columns: Gogebic (County), Located in: (Town/Range), Corner Code #. Row 1: Public Land Survey, T48N R 44W, I-6.

4. Lot No. , Recorded Plat
5. Private Claims

1/4 Corner 14 & 15; T.48 N., R.44 W.

Richard L. Drahn, in a field survey on October 14, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Cell (6, H) contains a black dot.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on Sept. 5, 1848. Original B.T.s --- Fir 7" S.34 W. 40 links (26.40') --- Cedar 12" N.56 W. 8 links (5.28')--- Corner restored by Richard L. Drahn RLS 21564 on 7/26/89 from the remains of the original Cedar B.T. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 6" (7") Sugar Maple N.17 W. (N.17 W.)3.78' (3.76') --- 7" (9") Red Maple S.66 E. (S.65 E.) 5.93' (5.93') --- 14" (14") Sugar Maple S.40 W. (S.40 W.) 16.35' (16.34') --- 6' Steel rail S.76 W. (S.75 W.) 2.2' (2.15') ---

Corner recorded in Gogebic County in Liber 3, Page 309 on 1/23/90.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. The original Cedar B.T. is now a 25" downed tree with GLO blazes and the reverse impression of the measuring notch. A 1935 era USFS Location poster is attached to the tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing tree referenced:

5" Sugar Maple S.88 W. 4.46'

PEER GROUP APPROVED
Richard L. Drahn 10/16/96
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date October 15, 1996

Surveyor's Michigan License No. 21564