

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
Gogebic County } ss.

Received for record the  
10<sup>TH</sup> day of JUNE  
A. D. 1996 at 11:00 o'clock  
A m., and recorded in  
Liber 5 of CORNERS

on page 396  
Ramona Collins, Deputy  
Register of Deeds

**Register of Deeds Stamp & File Number**

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- |                                       |                           |             |
|---------------------------------------|---------------------------|-------------|
| 1. Public Land Survey                 | T <u>48N</u> R <u>44W</u> | <u>I-10</u> |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
|                                       | T _____ R _____           | _____       |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____       |
|                                       | S _____ T _____ R _____   | _____       |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 26 & 27; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on June 1, 19 96  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established By Austin Burt on Sept. 6, 1848. Original B.T.s ---  
Hemlock 12" S.46 E. 19 links (12.54') --- Y. Birch 14" N.36 W. 33 links  
(21.78') --- Corner restored by Donald D. Lappale, RLS 12585 on 8/15/68  
from the remains of the two original bearing trees and natural feature  
ties south. He set a 2" dia. iron pipe with a 3" stamped brass cap and  
the following new B.T.s: --- 5" (9") Sugar Maple N.24 W.13.6' (13.54')  
--- 12" (16") Hemlock N. 31 E. (N.34 E.) 22.5' (22.41') --- 4" (7") Sugar  
Maple S.49 E. (S.30 E.) 21.1' (21.08') --- Corner recorded in Gogebic  
County in USFS Liber, Page T-17, on 3/31/69.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in  
parentheses above.

A stump hole remains from the original Hemlock B.T. and a Y. Birch stump,  
decayed to ground line remains from the original Y. Birch B.T.

**PEER GROUP APPROVED**

Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Bearing objects referenced:

- |                         |         |      |
|-------------------------|---------|------|
| 4" X 4" Cedar sign post | N.33 E. | 2.0' |
| 6' Steel sign rail      | S.67 W. | 2.5' |



Signed by Richard L. Drahn

Date June 2, 1996

Surveyor's Michigan License No. 21564