

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
Gogebic County } ss.

Received for record the  
10<sup>th</sup> day of JUNE  
A. D. 1996 at 11:00 o'clock  
A m., and recorded in  
Liber 5 of CORNERS  
page 397  
Ramona Collins, Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in  
Gogebic  
(County)

1. Public Land Survey	Located In: T <u>48N</u> R <u>44W</u>	Corner Code # <u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Sec. Cor. 26, 27, 34 & 35; T.48 N., R.44 W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard L. Drahn in a field survey on June 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on Sept. 6, 1848. Original B.T.s --- Fir 8" S.63 E. 14 links (9.24') --- Cedar 10" N.29 W. 15 links (9.90') --- Corner restored by Donald D. Lappala, RLS 12585 on 8/15/68 from the remains of the two original bearing trees, a line tree and natural feature tie north and west. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s : --- 9" (11") Cedar N.74 W. (N.73 W.) 9:0' (9.27') --- 4" (8") Cedar S.89 E. (S.86 E.) 17.6' (17.70') --- 3" (6") Cedar S.31 W. (S.36 W.) 7.8' (7.74') --- Corner recorded in Gogebic County in USFS Liber, Page V-17 on 3/31/69.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

A shallow depression remains from the original fir B.T. and the Cedar is now a badly decayed windfall.

PEER GROUP APPROVED  
Richard L. Drahn 6/6/96  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing objects referenced:

- 4" X 4" Cedar sign post N.48 W. 3.0'
- 6' Steel sign rail S.36 E. 2.5'



Signed by Richard L. Drahn Date June 2, 1996

Surveyor's Michigan License No. 21564