

**SURVEY &  
REMONUMENTATION**

OCT 03 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
10<sup>TH</sup> day of June  
A. D. 1996 at 11:00 o'clock  
A .m., and recorded in  
Liber 5 of CORNER  
page 398  
Ramona Collins, Deputy  
Register of Deeds

For corners in

Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> , R <u>44 W</u> .	<u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{2}$  Corner 34 & 35; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on June 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, on Sept. 6, 1848. Original B.T.s --- Cedar 14" S.46 E. 5 links (3.30') --- Cedar 6" N.36 W. 21 links (13.86')  
Corner restored by Donald D. Lappala, RLS 12585 on 9/15/72 from the remains of the two original bearing trees and from a natural feature tie and a line tree south. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 8" (10") Yellow Birch N.85 W. (N.86 W.) 17.8' (17.78") --- 7" (11") Yellow Birch N.05 W. (N.06 W.) 10.7' (11.06') --- 5' (7") Cedar S.38 E. (S.37 E.) 21.8' (21.72') --- Metal sign post N.66 W. (N.67 W.) 1.7' (1.75') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

Portions of cedar wood and roots remain from both of the Original B.T.s

**PEER GROUP APPROVED**  
Richard L. Drahn 6/6/96  
**COUNTY REPRESENTATIVE**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing tree referenced:

5" Yellow Birch N.37 E. 18.09'



Signed by Richard L. Drahn

Date June 1, 1996

Surveyor's Michigan License No. 21564