

MAY 1 6 2007

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }  
Gogebic County } ss.

Received for record the  
17<sup>TH</sup> day of OCTOBER  
A. D. 1996 at 9:50 o'clock  
A m., and recorded in  
Liber 6 of CORNERS

on page 69  
Ramona Collins Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

Gogebic  
(County)

Located In:

Corner Code #

- 1. Public Land Survey            T 48N R 44W            J-7  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_  
    T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   Property in Sec.              S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 14 & 23; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on October 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on Sept. 6, 1848. Original B.T.s --- Sugar 12" S.33 E. 35 links (23.10') --- Sugar 10" N.47 W. 5 links (3.30')  
Corner re-established by Richard L. Drahn, RLS 21564 on 7/27/89 using proportionate methods. He set a 3/4" solid aluminum rod with a 3 1/4" stamped aluminum cap and the following new B.T.s --- 12" (14") Sugar Maple N.24 W. (N.24 W.) 17.80' (17.82') --- 7" (7") Black Cherry S.13 W. (S.13 W.) 9.72' (9.69') --- 8" (8") Black Cherry S.68 W. (S.67 W.) 17.56' (17.56') --- 6" Steel rail N.30 E. (N.32 E.) 1.6' (1.59') ---  
Corner recorded in Gogebic County in Liber 3, Page 311 on 1/23/90.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. No evidence remains of the Original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing tree referenced:

9" Red Maple S.56 E. 22.62'

PEER GROUP APPROVED  
Richard L. Drahn 10/16/96  
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date October 15, 1996

Surveyor's Michigan License No. 21564