

10/16/96
 COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County }

Received for record the
17th day of OCTOBER
 A. D. 1996 at 9:50 o'clock
A m., and recorded in
 Liber 6 of CORNERS
 on page 70
Ramona Collins, Deputy
 Register of Deeds

For corners in

Gogebic
 (County)

Located In: Corner Code #

- 1. Public Land Survey
 T 48N R 44W K-1
 T ___ R ___
 T ___ R ___
 T ___ R ___
- 2. Property Controlling in Section
 S ___ T 49N R 44W K-13 (Onton.)
 S ___ T ___ R ___
 S ___ T ___ R ___
- 3. Miscellaneous Property in Sec.
 S ___ T ___ R ___
 S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

Sec. Cor. 1, 2, 35 & 36; T.48-49 N., R.44 W.

ONTONAGON COUNTY

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Drahn, in a field survey on October 7, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by Austin Burt on Aug. 17, 1847. Original B.T.s --- Sugar 14" N.35 E. 16 links (10.56') --- Sugar 12" N.50 W. 11 links (7.26') Corner restored by Richard L. Drahn, RLS 21564 on 10/17/83 from the stump remains of the original B.T.s, from line trees north, east & west and a natural feature tie north. He set a 30" long aluminum monument with a stamped 3 1/4" alum. cap and the following new bearing objects:--- 18" (20") Hemlock N.79 W. (N.81 W.) 66.49' (66.47') --- 14" Sugar Maple (15") N.64 E. (N.54 E.) 43.78' (43.75') --- 14" (16") Sugar Maple S.19 E. (S.20 E.) 41.79' (41.80') --- 6' Steel sign rail East (S.88 E.) 1.9' (1.85') ---
 Corner recorded in Gogebic County in Liber 2, Page 567, on 2/15/84.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. Stump holes are all that remain of the original B.T.s.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Bearing object referenced:

5" Sugar Maple N.28 W. 14.02'

PEER GROUP APPROVED
Richard L. Drahn 10/16/96
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date October 9, 1996

Surveyor's Michigan License No. 21564