

REGISTERED PROFESSIONAL SURVEYOR

MAY 1 6 1987

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } SR.

Received for record the
17TH day of OCTOBER
A. D. 19 96 at 9:50 o'clock
A. m., and recorded in
Liber 6 of CORNERS
on page 71.

Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44W</u>	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 1 & 2; T.48 N., R.44 W.

Richard L. Drahn, in a field survey on October 8, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by Austin Burt on Sept. 4, 1848. Original corner 18" Yellow Birch. Original B.T. Cedar 12" N.42 E. 7 links (4.62'). L. Chautelois on 9/29/35 recovered the GLO B.T., still scribed as a 14" Cedar. Corner restored by Donald D. Lappala, RLS 12585 on 8/21/68 in the center of the original Y. Birch corner tree and from the 14" Cedar stub with GLO blazes. He set a 2" iron pipe with a 3" stamped brass cap and the following new B.T.s --- 5" (9") Sugar Maple N.19 E. (N.25 E.) 16.3' (16.25') --- 6" (7") Red Maple S.73 E. (S.73 E.) 23.1' (22.98') --- 5" (8") Yellow Birch S.44 W. (S.44 W. 7.7' (7.62'))---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. Fragments of Y. Birch bark and wood remain from the GLO corner tree. Portions of decayed Cedar wood remain from the original B.T.

L. Chautelois's location poster relocated onto a 12" Hemlock bearing N.10 W. 7.45' from the corner. Tag unreadable.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

- 4" X 4" Cedar sign post N.26 E. 2.8'
- 6' Steel sign rail S.17 W. 2.96'

PEER GROUP APPROVED
Richard L. Drahn 10/16/96
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date October 9, 1996

Surveyor's Michigan License No. 21564