

MAY 18 1987

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
17th day of OCTOBER
A. D. 1996 at 9:50 o'clock
A m., and recorded in
6 of CORNERS

page 73
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in	Gogebic (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44W</u>		<u>K-4</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner 11 & 12; T.48 N., R.44 W.

Richard L. Drahn in a field survey on October 1, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner established by Austin Burt on 9/4/1848. Original B.T.s --- Sugar Maple 7" S.38 $\frac{1}{2}$ W. 23 links (15.18') --- Sugar Maple 10" N.56 E. 50 links (33.00') ---
 Corner restored by Donald D. Lappala, RLS 12585 on 8/8/68 from the remains of the two original B.T.s and line tree remains and natural feature ties north and south. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 4" Yellow Birch (7") N.14 E. (N.17 E.) 14.2' (14.21') --- 8" (11") Sugar Maple S.62 E. (S.60 E.) 17.5' (17.34') --- 4" (7") Sugar Maple S.74 W. (S.77 W.) 10.1' (10.04') ---
 Corner recorded in Gogebic County in USFS Liber, Page G-21 on 3/31/69.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Recovered the monument as described and the bearing trees as noted in parentheses above. Only a stump hole and a large shallow depression remains of the two original B.T.s.

Act 74 research form on file with Gogebic County records.

PEER GROUP APPROVED
Richard L. Drahn 10/16/96
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Bearing object referenced:

6' Steel sign rail S.24 E. 2.58'



Signed by Richard L. Drahn Date October 2, 1996
 Surveyor's Michigan License No. 21564