

MAY 18 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office
Gogebic County

Received for record on
17th day of OCTOBER
A. D. 1996 at 9:50 o'clock
A m., and recorded in
Liber 6 of CORNERS

on page 74
Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>44W</u>	<u>K-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 11, 12, 13 & 14; T.48 N., R.44 W.

Richard L. Drahn in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on Aug. 29, 1848. Original B.T.s --- Yellow Birch 20" S.70 W. 47 links (31.02') --- Yellow Birch 12" N.68 E. 17 links (11.22') ---
Corner restored by Donald D. Lappala, RLS 12585 on 8/8/68 from the remains of the N.68 E. B.T. and from line tree remains north, west and east. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s --- 6" (11") Black Ash N.05 W. (N.03 W.) 42.5' (42.45') --- 6" (10") Elm (dead Elm stub) N.31 E. (N.34 E.) 43.7' (43.82') --- 7" (12") Twin Black Ash S.89 E. (S.87 E.) 49.3' (49.24') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Recovered the monument as described and the bearing trees as noted in parentheses above. No evidence remains of the original B.T.s.

Act 74 research form on file with Gogebic County records.

REER GROUP APPROVED

Richard L. Drahn 10/16/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Bearing objects referenced:

- 8" Aspen S.58 W 21.31'
- 4" X 4" Cedar sign post S.01 W. 2.45'
- 6' Steel sign rail N.33 W. 2.26'



Signed by Richard L. Drahn

Date October 2, 1996

Surveyor's Michigan License No. 21564