

NOV 16 1987

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
17th day of OCTOBER
A. D. 1996 at 9:50 o'clock
A m., and recorded in
Liber 6 of CORNERS
on page 75
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in
Gogebic
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>48</u> N R <u>44</u> W	<u>K-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1/4 Corner 13 & 14; T.48 N., R.44 W.

I, Richard L. Drahn in a field survey on October 8, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by Austin Burt on August 29, 1848. Original B.T.s --- B. Ash 12" S.35 W. 22 links (14.52') --- B. Ash 14" N.50 E. 26 links (17.16') Corner re-established by Richard L. Drahn, RLS 21564, on 7/27/89 by single proportionate methods. He set a 3/4" X 7' aluminum rod with a 3 1/4" stamped alum. cap and the following new bearing trees: --- 9" (10") Black Ash S.20 E. (S.21 E. 13.69' (13.72') --- 10" (11") Black Ash S.68 W. (S.66 W.) 25.49' (25.45') --- 9" (10") White Birch N.31 E. (N.31 E.) 12.57' (12.59') --- 6' Steel rail N.60 W. (N.66 W.) 2.7' (2.69') ---
Corner recorded in Gogebic County in Liber 3, Page 312 on 1/23/90.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Act 74 research form on file with Gogebic County records.
Recovered the monument as described and the bearing trees as noted in parentheses above. No evidence remains of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Bearing tree referenced:
7" Cedar N.81 E. 34.82'

PEER GROUP APPROVED
Richard L. Drahn 10/16/96
COUNTY REPRESENTATIVE



Signed by _____ Date October 9, 1996

Surveyor's Michigan License No. 21564