

MAY 1 8 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Registrar's Office }
Gogebic County } ss.

Received for record the
17th day of OCTOBER

A. D. 1996 at 9:50 o'clock

A m., and recorded in
Liber 6 of CORNERS

on page 77

Ramona Collins Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in	Located in:	Corner Code #
Gogebic (County)		
1. Public Land Survey	T 48N R 44W	L-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 12 & 13; T.48 N., R. 44 W.

I, Richard L. Drahn in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established By Austin Burt on Aug. 29, 1848. Original B.T.s --- Y. Birch 12" S.47 W. 19 links (12.54') --- Sugar 10" N.67E. 16 links (10.56')

Corner restored by Richard L. Drahn, RLS 21564 on 1/7/79 from the remains of the two original B.T.s and from the remains of line trees east and west. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following new B.T.s --- 8" (10") Sugar Maple N. 40 W. 35.15' (N.39 W. 35.19') --- 8" (9") Sugar Maple S.85 E. (S.84 E.) 29.4' (29.44') --- 6" (8") Sugar Maple S.66 W. (S.69 W.) 35.4' (35.36') --- 7' Metal sign post N.19 W. (N.17 W.) 1.5' (1.05')

Corner recorded in Gogebic County in Liber 2, Page 17 on 2/12/80.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as noted in parentheses above. Only stump holes remain from the two original B.T.s.

Act 74 research form on file with Gogebic County records.

PEER GROUP APPROVED

Richard L. Drahn 10/16/96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing object referenced:

10" Sugar Maple S.26 E. 28.99'



Signed by *Richard L. Drahn*

Date October 2, 1996

Surveyor's Michigan License No. 21564