

**SURVEY & REMONUMENTATION**

SEP 08 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Register's Office }  
 Gogebic County } ss.

For corners in

Gogebic  
 (County)

Located In:

Corner Code #

- |                                    |   |     |   |     |      |
|------------------------------------|---|-----|---|-----|------|
| 1. Public Land Survey              | T | 47N | R | 44W | L-1  |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
|                                    | T |     | R |     |      |
| 2. Property Controlling in Section | S | 48N | R | 44W | L-13 |
|                                    | S |     | R |     |      |
| 3. Miscellaneous Property in Sec.  | S |     | R |     |      |
|                                    | S |     | R |     |      |

Received for record the  
14<sup>th</sup> day of MAY  
 A. D. 1998 at 3:20 o'clock  
P m., and recorded in  
 Liber 6 of CORNERS  
 on page 377

Ramona Collins Deputy  
 Register of Deeds  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 1 & 36; T.47-48 N., R.44 W.

Richard L. Drahn in a field survey on April 29, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by Austin Burt on 8/11/1847. Original B.T.s --- Fir 7" N.19 E. 45 links (29.70') --- Fir 9" N.17 W. 28 links (18.48') ---  
 Corner restored by Donald D. Lappala (12585) on 9/27/72 from the stumps of the two original B.T.s, a natural feature tie east and a recovered line tree west. He set a 2" X 60" iron pipe with a 3" stamped brass cap and;

5"	Red Maple	N.04 E.	14.7'
8"	Black Spruce	S.19 E.	63.8'
8"	Black Spruce	S.66 W.	49.7'
7'	Steel sign rail	N.11 W.	2.5'

Corner recorded in Gogebic County USFS Liber, Page Z-23 on 12/9/74.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

12"	Red Maple	N.06 E.	14.60' (new nail)
10"	Black Spruce	S.20 E.	dead and down
10"	black Spruce	S.64 W.	49.34' (new nail)
7'	Steel sign rail	S.08 W.	2.52'


No evidence remains of the original B.T.s.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

New bearing tree established:

10" Red Maple S.03 W. 43.89'

PEEB GROUP APPROVED  
Richard L. Drahn 5/13/98  
 COUNTY REGISTER



Signed by Richard L. Drahn

Date May 3, 1998

Surveyor's Michigan License No. 21564