

MAR 02 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

For corners in

Gogebic
(County)

Located In:

Corner Code #

1. Public Land Survey

T 48N R 45W. A-3

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

4. Lot No. , Recorded Plat

5. Private Claims

Section Corner 6, 7, 1 & 12; T.48 N., R.45-46 W.

I, Richard L. Drahn, in a field survey on August 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 9/10/1847. Original bearing trees:

Sugar 14" S.60 °W. 18 links (11.88')
Sugar 20" N.23° E. 38 links (25.08')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored corner position at record bearing and distance from the remains of the two original bearing trees. The first is very large windthrown stump hole. The second one is now is now a large series of root holes; species undetermined.

Corner research on file with Gogebic County records.

A 3/4" X 2' iron pipe and wood post set by Gogebic County Forestry Commission, set by compass and chain bears N.47 °W., 4.4' from the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree):

Sugar Maple 9" S.62° E. 20.81'
Yellow Birch 13" S.37° W. 22.14'
Yellow Birch 9" N.19° W. 30.18'
Steel sign rail 6' N.27° E. 2.04'

DEED GROUP APPROVED

Richard L. Drahn 8/24/99
COUNTY

Received for record the
26th day of AUGUST
A. D. 1999 at 1:40 o'clock
P m., and recorded in
Liber 7 of CORNERS
page 228
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Richard L. Drahn Date August 26, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1986