

MAR 02 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
Gogebic County } ss.

Received for record the
26TH day of AUGUST
A. D. 1999 at 1:40 o'clock
P m., and recorded in
Lib. 7 of CORNERS

page 229
Ramona Collins, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

For corners in SECTION

<u>Gogebic</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 48N R 45W.</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	<u>T 48N R 46W</u>	<u>M-4</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Quarter corner 7 & 12; T.48 N., R.45-46 W.

I, Richard L. Drahn, in a field survey on August 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt on 9/10/1847. Original bearing trees:

Y. Birch	12"	S.25° E.	34 links	(22.44')
Sugar	8"	N.25° W.	25 links	(16.50')

C.E. Haight and Wm. Beck, on 4/17/35 recovered a scribed Y. Birch and Sugar Maple at this location. They set a location poster on SW side of a 10" Hemlock. The corner lay SW 10 paces.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Restored the corner position at record bearing and distance from the remains of the two original bearing trees. The first is a badly decayed 20-24" Yellow Birch stump. The second one is now a stump hole with fragments of badly decayed Sugar Maple wood in the root holes.

Although unable to find the 1935 location poster, the tag tree is now a 15" Hemlock stub bearing N.40 E., 34.0'.

A 3/4" X 4' iron pipe bears S.01° W., 6.2'. A downed 4" X 5' squared Cedar post bears S.63° W., 4.5' from the original corner.

Corner research on file with Gogebic County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2" x 30" aluminum pipe monument with a 3 1/4" stamped aluminum cap and the following new B.T.s (all measurements taken to a nail in side of tree)

Sugar Maple	7"	N.15° E.	21.99'
Sugar Maple	8"	S.27° E.	27.46'
Sugar Maple	7"	N.78° W.	26.50'
Steel sign rail	6'	S.47° W.	2.35'

DEER GROUP APPROVAL
Richard L. Drahn 8/24/99
COUNTY REGISTER



Signed by Richard L. Drahn Date August 26, 1999

Surveyor's Michigan License No. 21564

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976

REVISED JAN., 1983

REVISED OCT., 1995