

SURVEY & REMONUMENTATION

SEP 08 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Register's Office }
 Gogebic County } ss.

Received for record the
18TH day of JUNE

A. D. 1998 at 1:25 o'clock
P m., and recorded in

Liber 7 of COGNRS

on page 5
Ramona L. Collins, De
 Register of Deeds

For corners in **SECTION**

Gogebic
 (County)

Located In: Corner Code #

- | | | | |
|------------------------------------|---------|------------------------|--------------|
| 1. Public Land Survey | | <u>T 48N R 45W</u> | <u>A-9</u> |
| | | <u>T _____ R _____</u> | <u>_____</u> |
| | | <u>T _____ R _____</u> | <u>_____</u> |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 19, 30, 24 & 25; T.48 N., R.45-46 W.

Richard L. Drahn, in a field survey on June 16, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/10/1847. Original B.T.s --- Y. Birch 12" S.30 W. 19 links (12.54') --- Y. Birch 20" N.10 E. 31 links (20.46') ---
 Corner restored by Richard L. Drahn (21564) on 6/19/84 from the stump hole of the first original B.T., line trees north, south, east and west and from recovered corners north, south, east and west. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and the following new B.T.s:

- | | | | |
|----|-------------|---------|--------|
| 6" | Sugar Maple | N.23 W. | 24.52' |
| 9" | Sugar Maple | S.08 W. | 36.52' |
| 7" | Sugar Maple | S.62 W. | 25.24' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | | |
|----|-----------------|---------|-------|
| 6' | Steel sign rail | S.84 E. | 2.15' |
|----|-----------------|---------|-------|

Corner recorded in Gogebic County in Liber 2, Page 659, on 12/10/84.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

- | | | | |
|-----|-----------------|---------|-------------------|
| 7" | Sugar Maple | N.25 W. | 24.53' |
| 10" | Sugar Maple | S.06 W. | 36.48' (new nail) |
| 9" | Sugar Maple | S.57 W. | 25.24' " " |
| 6' | Steel sign rail | S.89 E. | 2.17' |

A large windthrown stump hole is all that remains at S.30 W. of the B.T.s

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

- | | | | |
|----|-------------|---------|--------|
| 5" | Sugar Maple | S.77 E. | 17.74' |
|----|-------------|---------|--------|

DEED GROUP APPROVED
Richard L. Drahn 6/17/98
 COUNTY SURVEYOR



Signed by Richard L. Drahn

Date June 16, 1998

Surveyor's Michigan License No. 21564