

SEP 08 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Gogebic (County)

Located In: Corner Code #

- 1. Public Land Survey T 48N R 45W A-10
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 30 & 25; T.48 N., R.45-46 W.

I, Richard L. Drahn in a field survey on June 15, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 9/10/1847. Original B.T.s --- Y. Birch 15" N.11 W. 50 links (33.00') --- Ironwood 10" S.16 E. 23 links (15.18') --- Corner position re-established on 7/25/88 by Richard L. Drahn (21564) by single proportionate methods between recovered corners north and south. He set a 2" X 30" aluminum pipe with a 3 1/4" stamped aluminum cap and new B.T.s:

15"	Sugar Maple	N.48 W.	19.97'
20"	Sugar Maple	S.40 W.	18.28'
4"	Sugar Maple	S.71 W.	8.26'
6'	Steel sign rail	S.89 E.	1.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of the original survey corner or B.T.s remains.

Corner recorded in Gogebic County in Liber 3, Page 283, on 2/1/89.

Corner research on file with Gogebic County records.

Recovered the monument as described and the bearing trees as follows:

18"	Sugar Maple	N.49 W.	19.96'
20"	Sugar Maple	S.42 E.	18.25'
5"	Sugar Maple	S.72 W.	8.22' (new nail)
6'	Steel sign rail	N.86 E.	1.25'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

7" Sugar Maple N.60 E. 19.29'

PEER GROUP APPROVED
Richard L. Drahn 6/17/98
COURT RECORDED



Register's Office }
 Gogebic County } ss.

Received for record the
18TH day of JUNE

A. D. 19 98 at 1:25 o'clock
P m., and recorded in

Liber 7 of CORNERS
 on page 6.

Ramona L. Collins, Dep.
 Register of Deeds

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Signed by Richard L. Drahn

Date June 16, 1998

Surveyor's Michigan License No. 21564